

**WOOD CREEK PHASE III RESTORATION PROJECT**

**WOOD PROCUREMENT  
REQUEST FOR PROPOSALS**

**ADDENDUM #1  
ISSUED: MAY 6, 2025**

---

**THE FOLLOWING ADDITIONS, DELETIONS, AND/OR CHANGES SHALL BE MADE AND INCORPORATED IN THE CONTRACT DOCUMENTS.**

In **Attachment A to RFP – Log and Slash Procurement Specifications**, Item 2 shall be replaced with the following:

*“2. Log diameter shall be measured at mid-point along log length and shall not deviate by more than four inches less than or 6 inches greater than from the specified diameter;”*