

WOOD CREEK PHASE III RESTORATION PROJECT – REVEGETATION

REVEGETATION CONTRACTOR REQUEST FOR BIDS

ADDENDUM #1

ISSUED: MAY 20, 2025

THE FOLLOWING ADDITIONS, DELETIONS, AND/OR CHANGES SHALL BE MADE AND INCORPORATED IN THE CONTRACT DOCUMENTS.

1. Under Special Conditions Item 2(1)(B) Permits and Approvals in the Contract Documents, the following is added to the list of required permits and approvals that have not been issued:
 - 2) U.S. Fish and Wildlife Service’s Northwestern Pond Turtle Conservation Measures.
2. Attachment B, Section 01 15 00 (Measurement and Payment) No. 1.02 (F) Item 6 – Year 2 Invasive Control Area Treatment. Remove “wildlife relocation survey (for common species)”.
3. Attachment B, Section 31 17 09 (Revegetation Planting) No. 1.01 (C). Add number 12 to include the following:

If it is not possible to produce woody species with tight roots for the year-1 planting window, then these species would be planted in year-2 to permit ample growing time. If this were to occur, the locations of year-1 woody species planted in year-2 would be recorded, and the plant establishment period for these occurrences would follow the same schedule as the year-2 plant establishment period.
4. Attachment B, Section 31 17 09 (Revegetation Planting) No. 2.01 (A) to include the following:

Propagules may be collected from the project site and adjacent NRLT property (Freshwater Farms Reserve) in coordination with the respective landowners.
5. Attachment B, Section 31 17 09 (Revegetation Planting) No. 2.03. Add subsection (B) to include the following:

The size of plugs can either be:

 - 1 and 7/8 inches by 1 and 7/8 inches across and 2 and 3/8 inches deep which are referred to as “regular 50s”, or
 - 2 inches by 2 inches across and 5 inches deep, which are referred to as “deep 50s” or “DP50”.

There is no required root volume for the plugs, rather if the plant displays healthy vigor during the inspection period (prior to planting) then the root volume is assumed to be adequate.